

PRICE BID-(PART –B)

**Name of Work : ELEVATION OF EXISTING BOUNDARY WALL ALONG
THE DND IN BHEL TOWNSHIP, SEC-17, NOIDA**

**NIT No. : 09: AA: NOI: ADMN: Elevation BW: 112: 2015-16
Dated: 30.07.2015**

S. No.	Description of Item	Unit	Qty.	Rate (in Rs)	Amount
1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	cum	1.10		
2	Dismantling steel work manually/ by mechanical means in built up sections without dismembering and stacking within 50 metres lead as per direction of Engineer-in-charge.	kg	60.00		
3	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including disposal of excavated earth upto 50 m and lift upto 1.5 m, disposed soil to be levelled and neatly dressed : All kinds of soil 100.	sqm	81.00		
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	cum	2.00		
5	Reinforced cement concrete in walls(any thickness) including attached pilasters,buttresses,plinth and string courses column, pillars, piers, abutments, posts,struts, etc. upto floor five level, excluding the cost of centering, shuttering, finishing and reinforcement:1:2:4(1cement:2 coarse sand:4 graded stone aggregate 20 mm nominal size.)	cum	3.00		
6	Reinforced cement concrete in beams, suspende floors, roofs having slope upto 15 degree , landing, balconies, shelves, chajjas,lintels,bands,plain window sill,staircases and spiral staircases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement 1:2:4(1cement:2 coarse sand:4 graded stone aggregate 20 mm nominal size.)	cum	9.00		

7	Reinforcement of R.C.C. work including straightening, cutting, bending, placing in position and binding all complete - Thermo-Mechanically Treated bars.	kg	1080.00		
8	Centering and shuttering including strutting, propping etc. and removal for form of Lintles, beams, plinth beams, girders, bressumers and cantilevers.	sqm	70.00		
9	Centering and shuttering including strutting, propping etc. and removal for form of Columns, pillars, piers, Abutments, posts and Struts.	sqm	40.00		
10	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :Cement mortar 1:6 (1 cement : 6 coarse sand)	cum	60.00		
11	Washed stone grit plaster on exterior walls of height upto 10m above level in two layers, under layer 12mm cement plaster 1:4 (1 cement: 4 coarse sand) furrowing the under layer with scratching tool, applying cement slurry on the under layer @ 2kg of cement per square meter, top layer 15mm cement plaster 1:1/2:2 (1 cement: 1/2 coarse sand: 2 stone chipping 10mm nominal size) in panels with groove all round as per approved pattern including scrubbing and washing, the top layer with brushes and water to expose the stone chipping, complete as per specification and direction of Engineer-in-charge.	sqm	280.00		
12	12 mm cement plaster of mix 1:6 (1 cement: 6 coarse sand)	sqm	280.00		
13	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4 m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape (R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately).	mtr.	140.00		

14	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	sqm	184.00		
15	Total (Rs)				
16(a)	In case, as per the current status the party (service provider) is an Individual, HUF, or partnership firm including AOP	Service Tax (on.....% of total amount of SI No. 15) to be payable by party (.....%) (Rs)			
16(b)		Service Tax (on.....% of total amount of SI No. 15) to be payable by party (.....%) (Rs)			
17	In case, as per the current status the party is a Private or Public limited Company	Service Tax (on.....% of total amount of SI No. 15) to be payable by party (.....%) (Rs)			
18 (a)	Total Amount inclusive of Service Tax	In case of Individual, HUF,or partnership firm including AOP(Total of 15+16a+16b) (Rs)			
18(b)		In case of Private or Public limited Company (Total of 15+17) (Rs)			
Total Offer Value in Words : Rupees					

(Signature & seal of the contractor)