				Quality Plan for SS Central Bar, Top/Bottom Plate								QP:RM:GHAVP:02 Rev 00					
Suppl ier's LOGO	Supplier's Name and Address		Item : SS Central Bar and Top& Bottom Plate (DIN EN 10028-7, 1.4550/1.4571) Sub-system: Steam Generator			QP No.: To be filled by Supplier Rev.No.: To be filled by Supplier Date: To be filled by Supplier Page No:1 of 4				Proje W.O	ect: GH	1& 2 160-001-1-93-171					
SI. No	Component & Operations	Characteristics	Type of Check	Quantu m Of check	Referer Docum			C	mat of cord	Agency M B N			Remarks				
1.	2.	3.	4.	5.	6.		7.	8.	D*		9. **		10.				
1.0	Raw Material :								-								
1.1	Steel Melting : :Melting in electric furnace :Vacuum Degassing	Steel melting	Record Verification	100%	PC-M-961/01 MPP: To be submitted			тс	V	Р	R	R	Steel shall be fully killed.				
1.2	Ladle Analysis	Chemistry	Chemical analysis	1/Melt	PC-M-961/01 MPP: To be submitted			тс	V	Р	R	R					
1.3	Semi Product (Slab) casting	Free from defects	Visual/Record verification	100%	MPP: To be submitted			RD		Р		R					
2.0	In process Controls :							_									
2.1	Forming Process	Forming process	Record verification	100%	PC-M-961/ MPP: To be		itted	TC	\checkmark	Ρ	R		Method of Forming to be filled				
2.2	Marking after forming	Identifications	Verification and Visual	100%	PC-M-961 Rev 01			RD		Ρ	R						
2.3	Heat Treatment (Solution Annealing)	R.O.H , Soaking Temp & Time, R.O.C	Review of HT Chart	100%	PC-M-961 Rev 01 HT Plan: To be submitted			тс	V	Ρ	w	R	Chart shall be signed at the start and End of Heat treatment and submitted along with TC				

				LEGEND: * RECORDS, INDENTIFIED WITH "TICK" (√) SHALL BE ESSENTIALLY INCLUDED BY SUPPLIER IN QA DOCUMENTATION. ** M: SUPPLIER B: BHEL, N: NPCIL/TPI P: PERFORM R: REVIEW W: WITNESS AND H: HOLD TC:TEST CERTIFICATE RD:RECORD
Prepared	Reviewed & Approved	Reviewed & Approved	Reviewed & Approved	REALEST CERTIFICATE RD.RECORD
SUPPLIER	R'S NAME: To be filled	BHEL	NPCIL	

INTHIN. ork) S. LAKSHMI Bellin 18 S. LAKSHMI Deputy G. Joral Manager Quality Annurance BHEL, Trichy - 620 014.

		Quality Plan for SS Central Bar, Top/Bottom Plate						QP:RM:GHAVP:02 Rev 00						
Suppl ier's LOGO	ier's		Item : SS Central Bar and Top& Bottom Plate (DIN EN 10028-7, 1.4550/1.4571) Sub-system: Steam Generator			QP No.: To be filled by Supplier Rev.No.: To be filled by Supplier Date: To be filled by Supplier Page No:2 of 4				Project: GHAVP 1& 2 W.O : D157 to D160-001-1-93-171 P.O No: To be filled				
2.4	Identification of Test coupon and Cutting	Location and orientation	Visual & Measurement	100%	PC-M-96 MPP & M	1/01 ISTP: To be submitted	RD	\checkmark	Р	w	w			
2.5	Mechanical descaling	Surface Inspection , Free from Visual Defects	Visual	100%	PC-M-961/01 Free from Visual Defects		RD	V	Ρ			Surface Should be smooth and free of scales		
2.6	Pickling and Passivation of Plate	Completeness	Visual & passivity check	100%	PC-M-961/01 MPP: To be submitted		тс	\checkmark	Р	R				
2.7	Final Dimensional check	Dimensions	Measurement	100%	Drg No/P.O No: To be filled		тс	\checkmark	Р	R				
2.8	Ultrasonic Inspection (USI)	Internal soundness	Ultrasonic Test	100%	PC-M-961 Rev 01 EN10307 UT Procedure: To be submitted		тс	V	Р	w	w	Surface shall be cleaned after USI		
2.9	Specimens preparation	Dimensions	Measurement	100%	MSTP: T PC:M:96	o be submitted 1 Rev 01	RD		Р	w	w			
2.10	Mechanical and Metal	llurgical Tests :										_		
2.11	Product analysis	Chemistry	Chemical analysis	1 / Batch	PC-M-961 Rev 01 MSTP: To be submitted EN10028-7		тс	V	Р	w	R	Note-2		
2.12	Tensile at RT	Tensile Strength, Yield Strength (0.2% offset), % Elongation	Destructive Test	1/Batch	PC-M-961 Rev 01 MSTP: To be submitted EN10028-7		тс	V	Р	w	w	'		
2.13	Tensile at 350° C	Tensile Strength, Yield Strength (0.2% offset)	Destructive Test	1/Batch	PC-M-961 Rev 01 MSTP: To be submitted EN10028-7		тс	V	Р	w	w			

				LEGEND: * RECORDS, INDENTIFIED WITH "TICK" (√) SHALL BE ESSENTIALLY INCLUDED BY SUPPLIER IN QA DOCUMENTATION. ** M: SUPPLIER B: BHEL, N: NPCIL/TPI P: PERFORM R: REVIEW W: WITNESS AND H: HOLD TC:TEST CERTIFICATE RD:RECORD
Prepared	Reviewed & Approved	Reviewed & Approved	Reviewed & Approved	
SUPPLIER	S NAME: To be filled	BHEL	NPCIL	

(NITHIN . O.R)

Suppl ier's LOGO	Supplier's Name and Address			Item : 55 Centra Bottom Plate (D 1.4550/1.4571)	system: Steam Generator Page No:3 of 4					by Supplier by Supplier by Supplier by Supplier by Supplier by Supplier			
2.14	Corrosion Test (solution anneale condition)	•	Inter Granular Corrosion	IGC Test	1/Bat	tch ASTM A	PC-M-961 Rev 01 ASTM A 262 Practice-E MSTP: To be submitted		V	Р	w	w	Without sensitization
2.15	Corrosion Test (sensitization)	after	Inter Granular Corrosion	IGC Test	1/Bat	tch ASTM A	PC-M-961 Rev 01		V	Р	w	w	Sensitization-650° x 30 Minutes
2.16	Micrograph & gr size	rain	Micro structure, Grain Size	Micro test , Grain size check	1/Bat	ASTM E: tch MSTP: T Grain Siz	PC-M-961 Rev 01 ASTM E112		V	Р	w	R	
2.17	Hardness		Hardness	Brinell / Rockwell Hardness	1/Bat	cn I	PC-M-961 Rev 01 Value to be reported.		V	Р	w	w	
3.0	Final Inspection	on	•	•									
3.1	Visual Inspection	n	Free from visual defects	Verification and Visual	1009	% PC-M-96	1 Rev 01	тс	1	Р	w	R	
3.2	Marking		SI No, Heat Number, Material designation, Supply condition, Inspectors Seal, Manufactures name, P.O Number.	Verification and Visual	1004	% PC-M-96	1 Rev 01	тс	V	Ρ	w	w	
3.3	Mix up Test Positive Material Identification PMI Test 100% PC-M-961 Rev 01		тс	V	Р	w	R						
							BE ESSENT ** M: SL P: PERFOR	IALLY I IPPLIER	REVIEW	D BY SU EL, N: W: WIT	PPLIER NPCIL/ NESS /	WITH "TICK" (√) SHALL IN QA DOCUMENTATION. TPI NND H: HOLD	
Pr	Prepared Review		ed & Approved	Reviewed & Approve	ved Reviewe		d & Approved		TC:TEST CERTIFICATE RD:RECORD				

NPCIL

NORTHIN OR)

BHEL

SUPPLIER'S NAME: To be filled

		Quality Plan for SS Central Bar, Top/Bottom Plate								QP:RM:GHAVP:02 Rev 00				
Suppl ier's LOGO	Supplier S Malle and	l Address	Item : SS Central Bar and Top& Bottom Plate (DIN EN 10028-7, 1.4550/1.4571) Sub-system: Steam Generator		QP No.: To be filled by Rev.No.: To be filled by Date: To be filled by Su Page No: 4 of 4	olier	Project: GHAVP 1& 2 W.O : D157 to D160-001-1-93-171 P.O No: To be filled							
3.4	Certification and Documentation Control	Order compliance	Certificate compilation	100%	PC-M-961 Rev 01		тс	V	Р	R	R			
3.5	Decuments (Test Certificator) shall be sent to PHEL (Trichy prior to dispatch, Dispatch clearance will be given								Р	н	н			
3.6	Packing & Shipment	Packing	Visual	100%	6 PC-M-961 Rev 01				P	R	R	· ,		

Note:

MSTP (Material Sampling Plan), MPP(Manufacturing Process plan), Heat Treatment Plan, Ultrasonic test procedure shall be submitted by Supplier and the same will be subjected to both BHEL&NPCIL approval.
This Quality plan is applicable for SS Central bar(6t x50wx2104L) and Top &Bottom Plate(6tx90wx2042L)

676

				LEGEND: * RECORDS, INDENTIFIED WITH "TICK" (√) SHALL BE ESSENTIALLY INCLUDED BY SUPPLIER IN QA DOCUMENTATION. ** M: SUPPLIER B: BHEL, N: NPCIL/TPI P: PERFORM R: REVIEW W: WITNESS AND H: HOLD
Prepared	Reviewed & Approved	Reviewed & Approved	Reviewed & Approved	TC:TEST CERTIFICATE RD:RECORD
SUPPLIEF	X'S NAME: To be filled	BHEL	NPCIL	